

Water System Improvements, Yorktown, Indiana



Project: Well, Elevated Storage & Water Distribution Improvements

Engineering Cost: \$38,950

Construction Cost: \$1,250,000 Phase I
\$995,000 Phase II

Funding: Bonds and D.O.C.

Summary: The project included the upgrade of an existing well by providing a new deep well vertical turbine pump, well modifications, new chemical feed systems, new pump house building, supervisory control and data acquisition system for the control and monitoring of the waterworks facilities, standby power, and flow metering. Over 21,700 linear feet of water main extensions were completed. Also included in the project was a new 400,000 gallon single pedestal elevated tank along with rehabilitation of an existing 250,000 gallon multi-legged elevated tank.

Contact: Tim Kelty, Town Manager
9800 West Smith Street
Yorktown, IN 47396
Phone: 765-759-4003